

SAN RAFAEL CITY SCHOOLS  
310 Nova Albion Way San Rafael, CA 94903

ADDENDUM NO. 2  
TO

Davidson Middle School Portable Demolition Project  
# 20-08  
Addendum Date: 11/04/2020

THIS ADDENDUM:

1. Is temporary fencing required?
  - a. Yes. Contractor shall include and is responsible to put up and maintain temporary fencing of 8' high around the perimeter of the affected area. Temp fencing to at the minimum 1 drive through operable gate and 1 construction worker access gate. Temp fencing to be removed promptly at the end of the project. Access through the gates shall be locked when no construction personnel is onsite and managed by the contractor, providing access key or combo to the District Construction Manager.
  - b. Contractor to create a logistics plan and submit to the District for approval prior to mobilizing of the site.
2. What are the hours of construction?
  - a. Follow the noise ordinance mandated by the City of San Rafael.
  - b. For any work days immediately following a major holiday, the construction start time is 9am.
3. Is site restoration at the removed portables required?
  - a. In areas of the removed portables, contractor shall bring grade to a leveled surface with the surrounding and adjacent grass field by filling low area and cutting high area. Contractor to then perform fine grading and hydroseed.
  - b. At the new fence line, contractor to sawcut asphalt concrete in a straight line, then set a pressure treated header board of at minimum 2"x6" along the edge of asphalt."
4. Is abatement required?
  - a. Refer to the hazmat report included in the project manual. Contractor is responsible for abatement.

[END OF ADDENDUM]