

NOTICE

**San Rafael City School District
PROP. 39 ENERGY CONSERVATION AND ENERGY EFFICIENCY SERVICES
ENERGY MANAGEMENT SYSTEM FOR MULTIPLE SITES
REQUEST FOR QUALIFICATIONS AND PROPOSALS**

PROJECT

San Rafael City School District (DISTRICT) is requesting proposals from qualified Energy Management System vendors and contractors, herein referred to as ‘Contractor’ with experience working in K-12 educational settings. The DISTRICT has received funding from Proposition 39. A previous energy audit has identified energy efficiency opportunities in the installation of Energy Management Systems at District sites. The scope of this project includes designing, providing, and installing a new District-wide Energy Management with Mechanical Controls at each of the following sites: Bahia Vista Elementary School (ES), Coleman ES, Glenwood ES, Laurel Dell ES, San Pedro ES, Short ES, Sun Valley ES, Venetia Valley ES, Davidson Middle School, San Rafael High School, Terra Linda High School.

The selected Contractor will work with the assigned project manager, prepare final design documents, gather and submit verification data consistent with Prop 39 requirements, complete construction and installation, obtain required permits, register project with CA Department of Industrial Relations, and close out the project.

The DISTRICT will evaluate proposals to determine the Firm best qualified consistent with the evaluation criteria set forth, below. The DISTRICT intends to use the authority granted by Government Code sections 4217.10, et seq. as the basis for any contract award that may result from this Request for Qualifications and Proposals (RFQP).

It is the intent of this RFQP to establish the project approach, outline specifications and work-scope, schedule and terms and conditions governing the selection process. Proposals shall be firm for ninety (90) days from the date of their opening. All Proposals must meet or exceed all the specifications contained herein. Three (3) signed copies of the Proposal should be addressed to the attention of:

Dan Zaich, Sr. Director of Capital Facilities
San Rafael City School District
310 Nova Albion Way San Rafael, CA 94903

**The full RFQP and supporting documents are available on the DISTRICT'S website:
www.srcs.org/ Use the Bond Program Link to “Doing Business with Us”**

Proposals must be submitted by 5 p.m Feb. 21, 2019

PROCUREMENT

The project must conform to all requirements of California Government Code 4217, Title 24, California Division of State Architect (DSA) and all the parameters laid out in the Proposition 39 guidelines. Best value criteria, as set forth in the law, includes objective criteria related to price, features, functions and life-cycle costs.

The DISTRICT will evaluate proposals to determine the Firm best qualified consistent with the evaluation criteria set forth, below. The DISTRICT intends to use the authority granted by Government Code sections 4217.10, et seq. as the basis for any contract award that may result from this RFP.

PREVAILING WAGE RATES AND COMPLIANCE WITH SENATE BILL 854

This project is subject to compliance monitoring and enforcement by the California Department of Industrial Relations. In accordance with SB 854, all bidders, contractors and subcontractors working at the site shall be duly registered with the Department of Industrial Relations at the time of bid opening and at all relevant times.

The contractor will be required to furnish certified payroll records directly to the Department of Industrial Relations in accordance with Labor Code Sections 1771.4(a) and 1776.

SCOPE OF WORK

The Scope of Work is defined in **Exhibit B: Technical Specifications and Scope of Work**.

1. Furnish adequate invoices that detail material, labor and total project costs. These invoices will be submitted to the CA Energy Commission for reporting purposes.

GENERAL MATERIAL AND INSTALLATION REQUIREMENTS

1. Technical information regarding General Material and Installation requirements is contained in the **Exhibit B: Technical Specifications and Scope of Work**.
2. This is a design-build solicitation, product, equipment, materials selection must meet the requirements of the RFP but are the responsibility of the proposers.
3. System Installation shall conform to Manufacturers Installation Manual and approved project drawings and specifications.
4. Installation crews shall minimize disturbance (due to noise, dust, odors, moving of furniture and equipment) of building occupants and activities.
5. Sites shall be maintained and kept secure, free of excessive debris, and in safe condition during the construction period. Site should be left "broom clean" after work is complete at the end of each work day. All work should comply with the National Electrical Code,

the National Fire Code, and the California Building Code, and shall be inspected by DISTRICT inspectors at each appropriate phase.

EXISTING CONDITIONS

The contractor has had sufficient access to the facility and the facility electrical system to verify that the proposal includes all materials and labor for all system components specified in the attached **Exhibit B: Technical Specifications and Scope of Work**, and to verify the existing conditions to ensure the proper installation of the system. No additional payment will be made due to site conditions (excluding quantities) that were not accounted for by the Contractor, per the General Conditions.

CONTRACTOR USE OF PREMISES

1. All work during periods when school is not in session and on weekends shall be completed during regular business hours in conformance with the City of San Rafael requirements, between 7 am and 5 pm.
2. All work during the school year shall be completed after hours, between 4:00 p.m. and 11:00 p.m., Monday through Friday. The DISTRICT will accommodate work in unoccupied areas during operational hours.
 - a. The facility must remain open and operational during normal business hours, Monday through Friday, 6:00 a.m. to 6:00 p.m. All access to and from the facility must be maintained during these hours
3. Any utility shut-offs shall be scheduled through the Project Manager at least 72 hours ahead of time. Any shut-off that will impact the standard operation of the facility shall happen during off hours.

SCHEDULE

Date	Event
Jan. 23, 2019	RFP Issue
Jan. 30, 2019 9:00 a.m.	Pre-Proposal Job Walk—allow min. 6 hours
Feb. 7, 2019	End of questions and information request period
Feb. 14, 2019	Addendum sent out if needed
Feb. 21, 2019 – 5:00p.m.	Proposals Due at DISTRICT Offices, 310 Nova Albion Way, San Rafael CA 94903 Room 505
TBD	Announcement of Award and notice to proceed
March 11, 2019-- anticipated	Board action to approve best value contract
September 1, 2019	Project Completion

ADDITIONAL INSTRUCTIONS TO BIDDERS

1. Progress Payments will be made on a monthly basis upon certification by the District of the work completed to date.
2. Final Payment will be available after a walk-through ensures completeness and functionality to DISTRICT satisfaction and all requirements for training, warranty, punchlist, and Prop 39 reporting has been met, and after 30 days of uninterrupted operation.
3. Contractor is responsible for providing all materials, labor and necessary equipment to complete the work according to the specifications provided and best practices.
4. **Insurance Requirements.** Provide insurance as noted below. Provide certificates of insurance. Name the District as additional insured on General and Auto Liability.
 - a. Workers Compensation: Statutory Limits
 - b. Commercial General Liability: \$1,000,000 each occurrence, \$2,000,000 aggregate
 - c. Automobile Liability: \$1,000,000
5. Proposers shall visit the site areas and familiarize themselves with the scope of the project. A pre-bid meeting and project walk-through will be held on **Jan. 30, 2019**.
6. Following award of the contract, work may commence on or after **April 1, 2019**. All work must be completed on or before **September 1, 2019**.
7. The contractor shall clean their job area daily and dispose of all trash and debris leaving the area broom clean. The DISTRICT dumpsters are not to be used for contractor's trash.
8. It is the responsibility of the contractor / bidders to field verify all existing conditions.

QUALIFICATIONS

The DISTRICT may award a contract to the Contractor that, in its sole opinion, is the most capable of providing the range of services described in this RFP, and in the long-term best interest of the DISTRICT. The contractor shall be licensed in the state of California, hold a class B, C10, or C7 license, and shall be experienced completing similar types of work.

To be considered for this project a provider must demonstrate knowledge and experience in similar projects:

- California K-12 references that can attest to the quality of the Contractor's past work
- An established record of technical performance on similar projects within California
- A proven record of on-time and on-budget performance
- Excellent safety record
- Established records of the Contractor's ability to complete the work

- Credentialed, trained, and knowledgeable staff
- Competent management support at all levels
- Ability to effectively communicate with the DISTRICT, administration, staff, students, and community as needed

The DISTRICT reserves the right to investigate the qualifications of all Contractors under consideration and to confirm any part of the information furnished, or to require other evidence of managerial, financial, or technical capabilities that are considered necessary for the successful performance of the described energy efficiency project.

SUBMIT ALL REQUIREMENTS

Address the following items as completely as possible; response to each item is mandatory:

1. **COVER LETTER/LETTER OF INTEREST** Cover letter must include name of firm, address, telephone and fax numbers, and name of Principal to contact. Letter must be signed by representative of the firm with authorization to bind the firm by contract.
2. **PROJECT PROPOSAL**
 - a) Identify the project schedule (timeline)
 - b) Proposed cost by school site on a unit and total project basis, itemized budget, product quantity
 - c) Utilize Exhibit A: EMS Controls Scope Spreadsheet for preparation of proposal.
 - d) Data sheets of all equipment proposed for installation.
 - e) Energy and demand savings
 - f) Any measures requested but not included in the proposal should be itemized separately in the proposal and clearly marked as not included
 - g) Energy Management System Components Excel Proposal Sheet
 - h) Unit prices on Bid Pages will be used for contract changes that result from changes in quantities
3. **DESCRIPTION OF FIRM**
 - a) History, number of years in business in California, staff size
 - b) Location of office which will perform the work
 - c) Size of staff if applicable one-person Contractors/firms may submit
4. **RELEVANT EXPERIENCE**
 - a) List relevant K-12 public school projects where your firm has completed projects and include:

- i. Project name, type and location Ex: Classroom / Kitchen/ Library / Administration / Laboratory
 - ii. Year completed
 - iii. Project size, square feet and system cost
- b) List client names, contact person, and phone number for relevant project information.

5. FIRM TRACK RECORD

- a) Has your firm ever been let go by a client or replaced by another firm during any related project? If so, explain in detail.
- b) Does your firm have any current or pending litigation on any projects? If so, please describe.
- c) Has your firm defaulted on a contract within the past five (5) years or declared bankruptcy, or been placed in receivership within the past five (5) years?
- d) Is or has your firm been a party to suits, claims, or similar actions related to:
 - i. Construction claims relating to performance or delay
 - ii. OSHA, labor relations, or similar issues affecting the progress of the work
 - iii. California State Contractor License suspensions or code violations
 - iv. If "yes" to any of the above, provide a summary and current status of the issue under separate attachment to the response to this RFP.

SUBMITTAL INFORMATION

Deadline for submission of three (3) copies of your submittal is 5:00 PM, February 21, 2019. Submittals received after the deadline may be returned. All submittals become the sole property of the DISTRICT and the content will be held confidential until the selection of a firm is made. Any proprietary information must be designated clearly and should be bound separately and labeled with words "PROPRIETARY INFORMATION". An entire submittal marked as such will not be accepted.

Submit sealed proposals clearly marked "**RFP for District Wide Energy Management System**" to the following location:

Attn: Dan Zaich
Senior Director of Capital Facilities
San Rafael City School District
310 Nova Albion Way
San Rafael, CA 94903

Questions or clarifications may be submitted in writing to Dan Zaich by email (dzaich@srcs.org).

SUBMITTAL EVALUATION PROCESS

The DISTRICT Board will manage the selection process, review and evaluate the Proposals and make a recommendation regarding the selection of a successful Contractor by utilizing the DISTRICT's bid recap spread sheet which incorporates, Company, Sealed bids, Firms history, Relevant experience, Firm's track record, DIR identification number, Subcontractor list, Non-Collusion affidavit, Worker's Comp certificate, California contractor's license number and cost proposal. The review committee shall be comprised of individuals with experience, knowledge and program responsibility for the products and services of this Project. The evaluation, selection and recommendation timeframe is expected to be approximately two weeks.

Selection will be conducted comprehensively, fairly and impartially. Structured, quantitative scoring techniques will be used to maximize objectivity. Selection will include an assessment of the Firms' proven ability to apply their experience and technical expertise to:

- Complete this energy savings project in an efficient and skilled manner.
- Provide quality components per contract documents.
- Collect, document and assemble in the approved format, all pre and post monitoring and verification data as required of a Prop 39 energy savings project.

The DISTRICT will address the following criteria in evaluation of submittals in order to gauge the ability of the Provider. The same general criteria will be used to judge both the submittal and the interview, should the DISTRICT choose to conduct interviews with Providers.

1. Proposed contract price
2. Functions consistent with the Scope of Work attached and incorporated herein which shall consist of:
 - a. Meeting all scope of work criteria, without exception
 - b. Exceeding scope of work criteria
3. Features, other than core functions, which add tangible value expressed in the Proposal
4. Life-cycle costs which shall consist of:
 - a. Operational and maintenance costs
 - b. Replacement costs
 - c. Anticipated energy savings

The DISTRICT reserves the right to:

- Reject any or all submittals at its sole discretion.
- Cancel the Request for Proposals (RFP).

- Modify any requirements contained within the RFP and request a revised submission from all providers.
- Establish other evaluation criteria determined to be in the best interest of the DISTRICT.
- Contract with any of the firms responding to this RFP based solely upon its judgment of the qualifications and capabilities of the Contractor/firm.

A Selection Committee, as deemed necessary, will be formed to evaluate the submittals. Composition and creation of this committee, should one be formed, is at the sole discretion of the DISTRICT. The Selection Committee may review the submittals for format to ensure conformance with the requirements of the RFP and may select finalist to interview with the committee as part of the evaluation process. The DISTRICT does not guarantee that an interview will take place, thus reserving the right to select a Provider based solely on the information provided in the submittals received in response to the RFP. Should an interview take place, the key personnel responsible for fulfilling the requirements of the project shall be required to be present for the interview. The DISTRICT will take all steps necessary to ensure that any discussions and interviews conducted in connection to this RFP will be done in a fair and impartial manner.

This RFP does not commit the DISTRICT to negotiate a contract. The DISTRICT will not be responsible for any expenses incurred by any firm in preparing and submitting a proposal or response to this RFP.

SPECIAL PROCEDURES

1. Emergency Evacuation: Review and coordinate emergency response procedures with the facility staff. Become familiar with evacuation procedures and coordinate response of workers in an emergency.
2. Contractor Superintendent: Contractor's superintendent shall have experience supervising projects of similar size and type. The superintendent must be qualified to supervise all phases of this project. The superintendent's resume must be submitted to the DISTRICT prior to beginning the construction.
3. Project Safety
 - a. Contractor shall comply with all applicable safety standards from the California Code of Regulations, Title 8, including but not limited to the Construction Safety orders. For the duration of the Contract work the contractor must have on-site and available for review a copy of their injury and Illness Prevention Program. In addition, the contractor will be required to have the following documents at the job-site per Cal OSHA, Title 8 Regulations:
 - i. Code of Safety Practices
 - ii. Cal-OSHA required permits

- iii. All Cal-OSHA required training certifications
 - iv. Respiratory Protection Program for all work sited where respirators are mandatory.
 - v. Fall protection.
 - vi. Material Safety Data Sheets
- b. The contractor will be required to post all required Cal-OSHA documents.
 - c. The contractor must designate a superintendent as the Competent Person per Title 8.
 - d. The contractor must take appropriate measures to ensure the security and safety of the work site, and materials and tools stored on premises. No tools are to be left unsecured after hours for any reason, within the secure areas around or in the building. Employees shall be directed to diligently police the construction areas for removal of debris, as well as tools and materials. Notify employees that inappropriate behavior or language will be grounds for removal of that employee from the job site.
 - e. Comply with all safety recommendations of the Material Safety Data Sheets and ensure that workers, staff, and public are not exposed to hazardous fumes or materials as a result of this work.
 - f. Appropriate protective clothing shall be worn when handling the products. Clothing shall include hard hats, steel toe boots, and insulated gloves when working on an active system.

4. Project Meetings

- a. *Pre-construction Meeting:* The DISTRICT will schedule a pre-construction meeting with the Contractor, the contractor's Project Superintendent and affected DISTRICT department representatives and consultants, at DISTRICT facilities.
- b. *Project Progress Meetings:* The contractor will make arrangements for Project Progress Meetings held on a monthly basis. The Contractor will be responsible for scheduling, administering, preparing the agenda, and recording and distributing meeting minutes. Attendees shall include the Contractor's superintendent and the DISTRICT project manager. The agenda shall include, but not be limited to:
 - a. Review of work progress
 - b. Identification of problems that impede planned progress.
 - c. Maintenance of the Construction Schedule.
 - d. Corrective measures to maintain the Construction Schedule.
 - e. Planned progress in the succeeding work period.
 - f. Maintenance of quality of work standards.
 - g. Proposed changes to the schedule and project coordination, and the effect on the project.

- c. *Punch List Inspection:* The contractor will schedule a punch list inspection with the DISTRICT Project Manager. The inspection will allow the DISTRICT to identify problems that may impact the performance of the lighting system.
- d. *Final Inspection Meeting:* The Contractor will schedule a meeting that includes the DISTRICT Project Manager to walk-through and inspect the installation to ensure that all punch-list items have been addressed.

TEMPORARY FACILITIES

Telephone: The Contractor or supervisor on the job site must be able to be reached by phone at all times that work is in progress.

PROJECT CLOSEOUT

1. Clean all work areas, removing any debris.
2. Prepare three (3) copies of operating and maintenance manuals in hard cover binders and deliver to the DISTRICT. As a minimum the binders shall include:
 - i. A complete set of all approved submittals including shop drawings and product literature.
 - ii. Copies of all testing data and reports.

PROJECT SITES

Site	Address
San Rafael High School	150 3rd St, San Rafael, CA 94901
Bahia Vista	125 Bahia Way, San Rafael, CA 94901
Coleman	800 Belle Ave, San Rafael, CA 94901
Davidson	280 Woodland Ave, San Rafael, CA 94901
Glenwood	25 W Castlewood Dr, San Rafael, CA 94901
Laurel Dell	225 Woodland Ave, San Rafael, CA 94901
San Pedro	498 Point San Pedro Rd, San Rafael, CA 94901
Short	35 Marin St, San Rafael, CA 94901
Sun Valley	75 Happy Ln, San Rafael, CA 94901
Venetia Valley	177 N San Pedro Rd, San Rafael, CA 94903
Terra Linda High School	320 Nova Albion Way, San Rafael, CA 94903

EXHIBIT A

EMS CONTROLS BID SHEET & EMS CONTROL SCOPE

This is a separate worksheet attachment.

(EXCEL)

EXHIBIT B

TECHNICAL SPECIFICATIONS AND SOW

Exhibit B – Technical Specifications and Scope of Work

PART 1 - GENERAL

1.1 INTRODUCTION

- A. This section contains the technical specifications for the complete installation and integration of an Energy Management System for the District.
- B. The District is looking to control existing HVAC equipment and other energy using equipment through the design, procurement, and implementation of a complete Energy Management System (EMS).
- C. The District seeks an infinitely scalable solution, allowing for the integration of additional equipment in the future by adding sensors and controls to the EMS.
- D. The primary EMS in use across the District consists of an antiquated Alerton BACtalk system. A representative sample of EMS graphics has been made available by the District and is included as Attachment 3.
- E. The installation shall include all necessary components as described in this specification and any additional details not included in this specification that are necessary for properly completing the work.
- F. Contractor shall meet all code requirements and shall be responsible for and obtain all required State and/or local permits and inspections, including any Title 24 requirements deemed necessary.
- G. The installation shall be in conformance with the most current editions of the NEC (National Electric Code), California Electrical and Building Code, ACCA (Air Conditioning Contractors of America) Standard 5, Title 24, ASHRAE 135, CBC, ADA, and all other generally accepted standards for the installation of similar systems.

1.2 SYSTEM/SERVICE REQUIREMENTS

- A. Design, procure, and install complete EMS consisting of thermostats, and all necessary ancillary equipment that function together and integrate seamlessly with a new EMS front end interface.
- B. EMS shall be BACnet compatible (comply with ASHRAE 135). EMS interface shall be capable of being viewed and manipulated remotely and securely by means of an internet browser (Internet Explorer or equal). All points of the user interface shall be

accessible through standard PCs that do not require the purchase of any special software for off-site monitoring and management.

- C. EMS upgrades shall include the addition of a cloud-based system with an online interface capable of accessing from a standard PC, complete with (1) full EMS software license, new field controllers (as required), routers, bridges, and switches. Include dynamic graphics for all HVAC equipment and VAV temperature control zones. It is the intent of this project to interface as much of the existing EMS infrastructure as possible - including actuators, sensors, control wiring, and controllers - with the new EMS front-end. Hence, all proposed hardware and software must be fully capable of interfacing with existing systems. Vendor is to assume that existing equipment that is indoors is to be reused while outdoor equipment such as package unit controllers are to be replaced.
- D. EMS shall be fault-tolerant in the event of hardware or software failure, with defined procedures for system backup and restoration.
- E. All materials required for this work shall be of the latest proven technology, new and in original containers.
- F. Spare equipment shall be provided for any components of the EMS deemed to be essential, as well as any components used multiple times throughout the system. (e.g. wireless thermostats, wireless gateways, sensors). The number of spares provided for each piece of equipment shall be 5% of the total amount, or a minimum of one spare of gateways, controllers and thermostats
- G. Existing control points shall be maintained in the new EMS, and variable air volume (VAV) controllers and supply air temperature sensors to be included.

1.3 CONDUIT, WIRE

- A. All apparatus, conduit systems, etc. shall be installed and interconnected so as to form complete systems as herein. Contractor shall furnish and install all work necessary to make complete working systems.
- B. Patching and repair:
 - 1. Contractor is responsible for any patching and repairing of existing structures due to any installations during the project. If code requires thermostat locations to be moved, the contractor is responsible for installing thermostats

at code compliant height and patching and restoring hole left by old thermostat to match surrounding area.

C. Conduit:

1. Contract must use galvanized rigid steel conduits (RSC) for any new or replaced conduit used in outside or exposed areas. EMT conduit may be used for areas that are not exposed or hidden from view.
2. Contractor cannot utilize any existing conduit that contains fire detection wiring.

D. Wire:

1. All wire installed shall be of a standard manufacturer as approved by the National Board of Fire Underwriters and shall be of the size as required.
2. All wire shall bear the Underwriters' Laboratory label.
3. All power wiring conductors shall be type THWN or THHN copper.

1.4 SUBMITTALS

- A. The table below identifies each submittal that will be submitted by the Contractor to the District for review and approval. The District shall have five full working days to provide comments and an approval status. Contractor is responsible for addressing comments to the District's satisfaction.

Below is a summary table of required submittals:

Submittal	Description	Submittal Time
Equipment Specifications and Data Sheets	Provide manufacturer specifications (cut-sheets) for each thermostat, controllers, wireless gateway, and all other components	15 days after Notice to Proceed
System Design	Provide the system design for each location which identifies equipment to be installed. Also provide design narrative that shows how design meets technical requirements	15 days after Notice to Proceed
Final As-built Plans	An updated final inventory and plans with locations of thermostats, controllers, wireless gateways, and any other major components	5 days after completion

1.5 WARRANTY REQUIREMENTS

- A. Contractors must include a two (2) year warranty for all parts and labor. Warranty shall commence from the date of the project's Notice of Completion. These warranties shall include travel time and expense and provide on-site service and labor.
- B. Contractor is to maintain and not void warranty of equipment to be controlled which includes HVAC equipment during and after installation.

1.6 START-UP AND COMMISSIONING SERVICES

- A. Contractor shall be responsible for proper operation of all systems, minor subsystems, and services provided. Contractor is responsible for the start-up and commissioning of every unit controlled. All systems must be fully functional and operational after installation. If follow-up work is required to bring the system into compliance with the design intent, the District shall not be charged.
- B. Contractor shall be responsible for preparing a written commissioning and startup procedure including check off list and report format showing design conditions and blanks for indicating actual operating conditions. The report format shall include each piece of equipment and all items that require adjustment. Report to be submitted to the District 10 working days prior to execution of work for review and approval. A final report shall be provided once the final adjustments and/ or corrections are completed
- C. Personnel performing commissioning and startup services shall be fully qualified, experienced, and normally engaged in this type of work. If the Contractor does not have such personnel available from their own company, they shall hire, at their own expense, subcontractors who are qualified personnel.
- D. Functional performance tests verify that components, equipment, systems, and interfaces between systems operate correctly. They include operating modes, interlocks, control sequences, and responses to emergency condition.
- E. Functional performance testing and verification may be achieved by direct manipulation of system inputs (i.e. heating or cooling sensors), manipulation of system inputs by building automation system (i.e. software override of sensor

inputs), trend logs of system inputs and outputs using building automation system, or short-term monitoring of system inputs and outputs using stand-alone data loggers.

- F. If re-testing is necessary because any equipment or system reported to have been successfully started up or pre-functionally tested is found during functional testing to be faulty, the additional cost of retest shall be the responsibility of the Contractor.
- G. Final and complete commissioning, startup reports for all sites shall be submitted 10 working days prior to final acceptance and payment. This report shall be signed by each person doing the commissioning/startup task and by the responsible field person.

1.7 OPERATIONS AND MAINTENANCE MANUALS, TRAINING

- A. Contractor is to hold at least two 4-hour trainings for District staff on dates and times agreed upon by the District. Two bound hard copies, bound and tabulated, with a table of contents and an electronic copy (thumb drive) shall be provided to the District.
- B. Provide Operation and Maintenance manuals and documentation to District personnel 10 working days prior to date of Training.
- C. Utilize operation and maintenance manuals as basis for instruction. Review contents of manual with the District in detail to explain all aspects of operation and maintenance.
- D. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance. Prepare and insert additional data in operations and maintenance manuals when need for additional data becomes apparent during instruction.
- E. Contractor is responsible for videotaping the training sessions and providing District with physical and electronic copies of the trainings.
- F. Contractor shall provide the names, addresses, and telephone numbers of installing contractors and service representatives for equipment and control systems.

1.8 PROJECT CLOSEOUT

- A. Contractor shall provide as-built EMS drawings.

- B. Reconcile and close all permits.
- C. Restore all work areas to their original or better conditions
- D. Replace or repair to the District's satisfaction any building, infrastructure and/or systems damaged during the work.

Technical Specifications and SOW Attachment 1

Below is a summary of the sites for implementation of controls:

Site	Address
San Rafael High School	150 3rd St, San Rafael, CA 94901
Bahia Vista	125 Bahia Way, San Rafael, CA 94901
Coleman	800 Belle Ave, San Rafael, CA 94901
Davidson	280 Woodland Ave, San Rafael, CA 94901
Glenwood	25 W Castlewood Dr, San Rafael, CA 94901
Laurel Dell	225 Woodland Ave, San Rafael, CA 94901
San Pedro	498 Point San Pedro Rd, San Rafael, CA 94901
Short	35 Marin St, San Rafael, CA 94901
Sun Valley	75 Happy Ln, San Rafael, CA 94901
Venetia Valley	177 N San Pedro Rd, San Rafael, CA 94903
Terra Linda	320 Nova Albion Way, San Rafael, CA 94903

Below is a summary of the equipment to be controlled at each site. Please refer to the mechanical inventory for details.

Site	Cooling Units	Electric Heat/ Heat Pumps	Boilers/ Furnaces	VAVs/ AHUs	Split System HVAC
San Rafael High School	9	7	10	2	-
Bahia Vista	4	-	27	16	-
Coleman	23	-	-	1	19
Davidson	5	8	16	-	-
Glenwood	-	1	9	-	-
Laurel Dell	6	-	-	-	-
San Pedro	1	-	13	3	-
Short	1	1	3	-	-
Sun Valley	5	2	11	-	4
Venetia Valley	6	1	-	-	-
Terra Linda	18	-	45	-	2

Technical Specifications and SOW Attachment 2

SIRS - Mechanical Inventory	Location - Building		Location - Floor		Drawing Notation		Equipment Type		Make		Model #		# Units In Scope		279 SUPPLY FAN		GAS FIRED FURNACE			MOTOR				Comments	Column 1	
School	Building	Location	Floor	Location	Floor	Notation	Type	Model	Make	Model	Make	Model	Model	Model	Model	HTG	HTG	GAS INPUT	OUTPUT	COMB. EFF.	FLA	MOCP	SHET	DATE		
San Rafael High School	BLDG 1	ROOTTOP	AC-1	AC-1	AC-1		FORCED-AIR FURNACE	TRANE	YHCO38A3	Y	1600	NA	NA	60	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1		
San Rafael High School	BLDG 1	ROOTTOP	AC-2	AC-2	AC-2		FORCED-AIR FURNACE	TRANE	YHCO38A3	Y	1200	NA	NA	60	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1		
San Rafael High School	BLDG 1	ROOTTOP	AC-3	AC-3	AC-3		FORCED-AIR FURNACE	TRANE	YHCO38A3	Y	1200	NA	NA	60	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1		
San Rafael High School	BLDG 1	ROOTTOP	AC-4	AC-4	AC-4		FORCED-AIR FURNACE	TRANE	YHCO38A3	Y	1400	NA	NA	60	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1		
San Rafael High School	BLDG 1	ROOTTOP	AC-5	AC-5	AC-5		FORCED-AIR FURNACE	TRANE	YHCO72A3	Y	3200	NA	NA	120	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1		
San Rafael High School	BLDG 1	F-1					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	F-2					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	F-3					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	F-4					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	F-5					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	F-6					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	F-7					FORCED-AIR FURNACE	TRANE	TUX100C560A	Y	1800	0.2	3/4	100	92	92%	119/V/01	13.5	15	M4.1	1/21/06	1				
San Rafael High School	BLDG 1	COUNSELOR	EMH-1				BASEBOARD HEATER	TRANE	E1515 TYPE D&F	Y	NA	NA	NA	NA	NA	NA	NA	119/V/01	13.5	15	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	ROOTTOP	HV-11	HEATING & VENTING MAU			STERLING	PV0046	Y	6900	NA	7-1/2	600	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	ROOTTOP	HV-12	HEATING & VENTING MAU			STERLING	PV0046	Y	1000	NA	1/2	100	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	SAC-A1	AC UNIT				MITSUBISHI	FX18F-K3	Y	NA	NA	NA	NA	NA	NA	NA	119/V/01	NA	NA	NA	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	SAC-A2	AC UNIT				MITSUBISHI	FX18E-K3	Y	NA	NA	NA	NA	NA	NA	NA	119/V/01	NA	NA	NA	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	CU-1	CONDENSING UNIT				MITSUBISHI	PU18E-K	Y	NA	NA	NA	NA	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	CU-2	CONDENSING UNIT				MITSUBISHI	PU18E-K	Y	NA	NA	NA	NA	NA	NA	NA	208/V/02	NA	NA	NA	M4.1	1/21/06	1			
San Rafael High School	BLDG 1	HC-1	HEATING COIL				TRANE	TYFE W	Y	740	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.2	1/21/06	1		
San Rafael High School	BLDG 1	HC-2	HEATING COIL				TRANE	TYFE W	Y	580	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.2	1/21/06	1		
San Rafael High School	BLDG 1	HC-3	HEATING COIL				TRANE	TYFE W	Y	255	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.2	1/21/06	1		
San Rafael High School	BLDG 1	HC-4	HEATING COIL				TRANE	TYFE W	Y	195	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.2	1/21/06	1		
San Rafael High School	BLDG 1	HC-5	HEATING COIL				TRANE	TYFE W	Y	600	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.2	1/21/06	1		
San Rafael High School	BLDG 1	HC-6	HEATING COIL				TRANE	TYFE W	Y	72	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.2	1/21/06	1		
Div-440m	30b	CLASROOM	F-1	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1800	0.4	1/2	100	93	93%	120/V/01	13.5	15	M4.1	1/21/04	1					
Div-440m	30c	CLASROOM	F-2	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1800	0.4	1/2	100	93	93%	120/V/01	13.5	15	M4.1	1/21/04	1					
Div-440m	30c	CLASROOM	F-3	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1800	0.4	1/2	100	93	93%	120/V/01	13.5	15	M4.1	1/21/04	1					
Div-440m	30c	CLASROOM	F-4	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1800	0.4	1/2	100	93	93%	120/V/01	13.5	15	M4.1	1/21/04	1					
Div-440m	30c	CLASROOM	F-5	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1800	0.4	1/2	100	93	93%	120/V/01	13.5	15	M4.1	1/21/04	1					
Div-440m	30c	CLASROOM	F-6	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	680	0.4	1/3	60	55	92%	120/V/01	8.3	15	M4.1	1/21/04	1					
Div-440m	10c	ROOTTOP	AC-1	AC UNIT			TRANE	YHCO50A3	Y	1900	NA	NA	60	NA	NA	NA	208/V/01	NA	NA	NA	M4.18	1/21/04	1			
Div-440m	10c	1ST FLOOR	HC-1	HEATING COIL			TRANE	TYFE W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	10c	1ST FLOOR	HC-2	HEATING COIL			TRANE	TYFE W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	10c	1ST FLOOR	HC-3	HEATING COIL			TRANE	TYFE W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	10c	1ST FLOOR	HC-4	HEATING COIL			TRANE	TYFE W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	10c	1ST FLOOR	HC-5	HEATING COIL			TRANE	TYFE W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	10c	ROOTTOP	HC-7	HEATING COIL			TRANE	TYFE W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	10c	ROOTTOP	HC-8	HEATING COIL			TRANE	TYFE W	Y	600	NA	NA	NA	NA	NA	NA	NA	208/V/01	NA	15	M4.18	1/21/04	1			
Div-440m	30b	LIBRARY LAB	ACS-1	AC UNIT			CARRIER	4042A024	Y	NA	NA	NA	NA	NA	NA	NA	NA	208/V/01	NA	30	M4.18	1/21/04	1			
Div-440m	30b	LIBRARY LAB	CU-1	AC UNIT			CARRIER	31H0024	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.18	1/21/04	1		
Div-440m	GYM	PT/BLDG	F-7	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1950	0.5	3/4	120	111	92%	119/V/01	13.5	15	M4.01	1/19/04	1					
Div-440m	GYM	PT/BLDG	F-8	FORCED-AIR FURNACE			TRANE	TUX100C560A	Y	1800	0.5	3/4	120	111	92%	119/V/01	13.5	15	M4.01	1/19/04	1					
Div-440m	GYM	PT/BLDG	F-9	FORCED-AIR FURNACE			CARRIER	52H0450-08	Y	700	0.5	1/2	40	33	92%	119/V/01	4.9	15	M4.01	1/19/04	1					
Div-440m	GYM	LOCKER ROOM	CU-8	CONDENSING UNIT			CARRIER	38H00418	Y	NA	NA	NA	NA	NA	NA	NA	208/V/01	NA	NA	NA	M4.01	1/19/04	1			
Div-440m	GYM	ROOTTOP	CU-9	CONDENSING UNIT			CARRIER	38H002074	Y	NA	NA	NA	NA	NA	NA	NA	208/V/01	NA	NA	NA	M4.01	1/19/04	1			
Div-440m	42b	CLASSROOM	F-1	FORCED-AIR FURNACE			CARRIER	58HFK-010-20	Y	1600	0.8	3/4	80	74	92%	120/V/01	14.1	20	M0.2	2/15/02	1					
Div-440m	42b	CLASSROOM	F-2	FORCED-AIR FURNACE			CARRIER	58HFK-010-20	Y	1600	0.8	3/4	80	74	92%	120/V/01	14.1	20	M0.2	2/15/02	1					
Div-440m	42b	CLASSROOM	F-3	FORCED-AIR FURNACE			CARRIER	58HFK-010-20	Y	1600	0.8	3/4	80	74	92%	120/V/01	14.1	20	M0.2	2/15/02	1					
Div-440m	42b	CLASSROOM	F-4	FORCED-AIR FURNACE			CARRIER	58HFK-010-20	Y	1600	0.8	3/4	80	74	92%	120/V/01	14.1	20	M0.2	2/15/02	1					
Div-440m	42b	CLASSROOM	F-5	FORCED-AIR FURNACE			CARRIER	58HFK-010-20	Y	1600	0.8	3/4	80	74	92%	120/V/01	14.1	20	M0.2	2/15/02	1					
Div-440m	42b	CLASSROOM	F-6	FORCED-AIR FURNACE			CARRIER	58HFK-010-20	Y	1600	0.8	3/4	80	74	92%	120/V/01	14.1	20	M0.2	2/15/02	1					
Venetia Valley	ROOFSTOP-B	ROOT	AC-1	AC/DC AC UNIT			TRANE	YHCO50A3	Y	1950	0.5	3/4	100	92	92%	119/V/01	13.2	15	M4.01	1/19/05	1					
Venetia Valley	ROOFSTOP-C	ROOT	AC-2	AC/DC AC UNIT			TRANE	YHCO50A3	Y	1950	0.5	3/4	100	92	92%	119/V/01	13.2	15	M4.01	1/19/05	1					
Venetia Valley	BLDG A	Admin	CU-1	CONDENSING UNIT			CARRIER	38H2007	Y	1200	NA	NA	NA	NA	NA	NA	208/V/01	NA	NA	NA	M4.01	4/23/04	FEEDS AH-1			
Venetia Valley	BLDG A	Admin	CU-2	CONDENSING UNIT			CARRIER	38H2007	Y	1200	NA	NA	NA	NA	NA	NA	208/V/01	NA	NA	NA	M4.01	4/23/04	FEEDS AH-2			
Venetia Valley	KINDER	1	AC-1	AC UNIT			BAFO	WAG40A	Y	1000	NA	NA	NA	NA	NA	NA	208/V/03</td									

School	Location - Building	Location - Floor	Drawing Notation	Equipment Type	Make	Model #	Include In Scope	# Units In Scope			27) SUPPLY FAN		GAS FIRED FURNACE		MOTOR				Comments	Column 1	
								Htg	Gas Input	Output	CDR/L Eff (%)	V/H2/P	FLA	MOPC	SH/ET	Date					
Bahia Vista			F-C3	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C4	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C5	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C6	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C7	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C8	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C9	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C10	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C11	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C12	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C13	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista			F-C14	FORCED-AIR FURNACE	TRANE	TUX100C442A	Y	1700	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01	1/18/05	1		
Bahia Vista	BLDG A	ROOFTOP	AC-1	AC UNIT	TRANE	YOH151	Y	5000			150	208V/60/3	92	92%	120V/60/3	15	15	M4.01	1/18/05	1	
Bahia Vista	BLDG B	ROOFTOP	AC-2	AC UNIT	TRANE	TOR100	Y	12000			2000	208V/60/3	250	250%	120V/60/3	250	250	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-1	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-2	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-3	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-4	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-5	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-6	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-7	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-8	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	VAV/1-9	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-1	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-2	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-3	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-4	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-5	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-6	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	2nd	VAV/2-7	VARIABLE AIR VOLUME	TRANE	VCF1	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	B-1	BOILER	BRYAN	F-650-W	Y	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1	
Bahia Vista	BLDG B	1st	ACS-1	AC UNIT	CARRIER	FGA136	Y	1000	0.5	1/2	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1
Bahia Vista	BLDG B	ROOFTOP	CU-1	AC UNIT	CARRIER	FGA136	Y	1000	0.5	1/2	NA	NA	NA	NA	NA	NA	NA	NA	M4.01	1/18/05	1
Coleman	BLDG A	MECHANICAL	F1	SPLIT SYSTEM	REHDER	SLXH150	Y	2400	0.5	1	150	120	89%	120V/60/1	6.2	NA	M4.02	6/7/03	1		
Coleman	BLDG A	MECHANICAL	F2	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG B	MECHANICAL	F3	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG B	KINDERGARTEN	F4	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG B	KINDERGARTEN	F5	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG E	CLASSROOM	F6	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG E	CLASSROOM	F7	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG E	CLASSROOM	F8	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG F	CLASSROOM	F9	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG F	CLASSROOM	F10	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG G	CLASSROOM	F11	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG G	CLASSROOM	F12	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG G	CLASSROOM	F13	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG G	CLASSROOM	F14	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG H	CLASSROOM	F15	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG H	CLASSROOM	F16	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG H	CLASSROOM	F17	SPLIT SYSTEM	CARRIER	SMXVA100-20	Y	2000	0.5	3/4	80	74.5	92%	120V/60/1	14.1	20	M2.02	6/7/03	1		
Coleman	BLDG I	DAYCARE	F18	SPLIT SYSTEM	CARRIER	SMXVA100-16	Y	1600	0.4	1/2	60	55.9	92%	120V/60/1	9.5	20	M2.02	6/7/03	1		
Coleman	BLDG J	TOILET	CU1	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	60	M2.02	6/7/03	1	
Coleman	BLDG K	TOILET	CU2	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	60	M2.02	6/7/03	1	
Coleman	BLDG B	CLOSET	CU3	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	60	M2.02	6/7/03	1	
Coleman	BLDG B	CLOSET	CU4	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	50	M2.02	6/7/03	1	
Coleman	BLDG B	KINDERGARTEN	CUS	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	50	M2.02	6/7/03	1	
Coleman	BLDG E	CLASSROOM	CU6	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	50	M2.02	6/7/03	1	
Coleman	BLDG E	CLASSROOM	CU7	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	60	M2.02	6/7/03	1	
Coleman	BLDG F	CLASSROOM	CU8	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	50	M2.02	6/7/03	1	
Coleman	BLDG G	CLASSROOM	CU9	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	50	M2.02	6/7/03	1	
Coleman	BLDG G	CLASSROOM	CU11	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	60	M2.02	6/7/03	1	
Coleman	BLDG G	CLASSROOM	CU13	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	50	M2.02	6/7/03	1	
Coleman	BLDG G	CLASSROOM	CU14	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1	NA	60	M2.02	6/7/03	1	
Coleman	BLDG H	CLASSROOM	CU15	CONDENSING UNIT	CARRIER	3BTFA00	Y	NA	NA	NA	NA	NA	NA	NA	208V/60/1						

SRCS - Mechanical Inventory																			
School	Building	Location - Floor	Drawing Notation	Equipment Type	Make	Model #	Include in Scope	279 SUPPLY FAN			GAS FIRED FURNACE			MOTOR			Comments	Column#	
								HTG	FSP	HP	(MBH)	OUTPUT	COMB. EFF (%)	V/HZ/P	FLA	MOCP	SHEET	DATE	
Glenwood	G	G09	F-1	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.5	15	M4.1	8/1/03	1
Glenwood	G	G09	F-2	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.5	15	M4.1	8/1/03	1
Glenwood	G	G04	F-3	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.5	15	M4.1	8/1/03	1
Glenwood	G	G03	F-4	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.5	15	M4.1	8/1/03	1
Glenwood	G	G02	F-5	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.5	15	M4.1	8/1/03	1
Glenwood	G	G01	F-6	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.5	15	M4.1	8/1/03	1
Glenwood	B1	DAYCARE	F-7	FORCED-AIR FURNACE	TRANE	TU100C960C	Y	2160	0.5	3/4	100	93	93%	120V/60/1	12.9	15	M4.1	8/1/03	1
Glenwood	H	H01	F-8	FORCED-AIR FURNACE	TRANE	TU100C945C	Y	1800	0.4	1/2	100	93	93%	120V/60/1	12.9	15	M4.1	8/1/03	1
Glenwood	H	H03	F-9	FORCED-AIR FURNACE	TRANE	TU040C924	Y	950	0.4	1/5	40	38	93%	120V/60/1	4.7	15	M4.1	8/1/03	1
Glenwood	B1	B12	EBU-1	ELECTRIC HEATER	Q-MARK	CW191204	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60			M4.1	8/1/03	1
Laurel Dell	BLDG 300	ROOFTOP	AC-1	AC UNIT	TRANE	YH0400	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60	N/A	N/A		3/15/05	1
Laurel Dell	BLDG 300	ROOFTOP	AC-2	AC UNIT	TRANE	YH0415	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60	N/A	N/A		3/15/05	1
Laurel Dell	BLDG 300	ROOFTOP	AC-3	AC UNIT	TRANE	YH0436	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60	N/A	N/A		3/15/05	1
Laurel Dell	BLDG 100	ROOFTOP	AC-4	AC UNIT	TRANE	YH0416	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60	N/A	N/A		3/15/05	1
Laurel Dell	BLDG 100	ROOFTOP	AC-5	AC UNIT	TRANE	YH0448	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60	N/A	N/A		3/15/05	1
Laurel Dell	BLDG 100	ROOFTOP	AC-6	AC UNIT	TRANE	YH0448	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/1/60	N/A	N/A		3/15/05	1
San Pedro	EAST BLDG	In class	F-4	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	EAST BLDG	In class	F-5	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	EAST BLDG	In class	F-6	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	EAST BLDG	In class	F-7	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	EAST BLDG	In class	F-8	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	MFR	ART ROOM	F-9	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	MFR	MUSIC ROOM	F-10	FORCED-AIR FURNACE	TRANE	TU100C442A	Y	1800	0.5	3/4	100	92	92%	115V/60/1	13.5	15	M4.01A	11/1/204	1
San Pedro	EAST BLDG	FOOTTOP	AC-2	AC UNIT	TRANE	YH0448A3	Y	1600	N/A	N/A	N/A	N/A	N/A	230V/60/3	N/A	N/A		NO DRAWINGS	1
San Pedro	EAST BLDG	FOOTTOP	HV-1	HEAT VENT UNIT	TRANE	GRA101G050	Y	2000	N/A	2	N/A	N/A	N/A	208V/60/3	N/A	N/A		NO DRAWINGS	1
San Pedro	EAST BLDG	FOOTTOP	HV-2	HEAT VENT UNIT	TRANE	GRA101G050	Y	5000	N/A	5	N/A	N/A	N/A	208V/60/3	N/A	N/A		NO DRAWINGS	1
San Pedro	EAST BLDG	EXTERIOR	HV-4	HEAT VENT UNIT	TRANE	GRA101G050	Y	150	N/A	1.5	N/A	N/A	N/A	208V/60/3	N/A	N/A		NO DRAWINGS	1
Short	BLDG 10	CLASS 1		FORCED-AIR FURNACE			Y											NO DRAWINGS	1
Short	BLDG 10	CLASS 2		FORCED-AIR FURNACE			Y											NO DRAWINGS	1
Short	BLDG 10	CLASS 3		FORCED-AIR FURNACE			Y											NO DRAWINGS	1
Short	BLDG 10	CLASS 4		FORCED-AIR FURNACE			Y											NO DRAWINGS	1
Short	BLDG 10	CLASS 5		FORCED-AIR FURNACE			Y											NO DRAWINGS	1
Short	BLDG A	CLASSROOM 1	F-1	GAS FIRED FURNACE	CARRIER	SEMTB-050-12	Y	1000	0.5	N/A	60/23	56/27	93	115V/60/1	8.4	N/A	M1.0	8/16/11	1
Short	BLDG A	CLASSROOM 2	F-2	GAS FIRED FURNACE	CARRIER	SEMTB-050-12	Y	1000	0.5	N/A	60/23	56/27	93	115V/60/1	8.4	N/A	M1.0	8/16/11	1
Short	BLDG A	OFFICE	F-3	GAS FIRED FURNACE	CARRIER	SEMTB-100-20	Y	1500	0.7	N/A	100/65	94/65	93	115V/60/1	13.3	N/A	M1.0	8/16/11	1
Short	BLDG A	EXTERIOR	CU-1	AIR COOLED CONDENSER	CARRIER	2AP7050-30	Y	1500	N/A	N/A	N/A	N/A	N/A	208V/60/1	24.3	N/A	M1.0	3/7/11	1
Short	BLDG A	CLASSROOM	F-4	HEAT PUMP	MOD.TECH		Y							208V/7/1	6.2	N/A	M1.02	4/29/14	1
Sun Valley	BLDG E	FOOTTOP	AC-1	HVAC UNIT	CARRIER	48H014	Y	4700	0.5	3/4	200	200	80%	208V/60/3	NA	70		3/25/03	1
Sun Valley	BLDG E	FOOTTOP	AC-2	HVAC UNIT	CARRIER	48H015	Y	4700	0.5	3/4	250	200	80%	208V/60/3	NA	71		3/25/03	1
Sun Valley	BLDG E	MUSIC ROOM	F-15	SPLIT SYSTEM	CARRIER	SEMYA1050-16	Y	1500	0.5	1/2	60	56	93%	120V/60/1	8.4	15	M1.2	5/21/03	1
Sun Valley	BLDG E	CLASSROOM 04	F-16	SPLIT SYSTEM	CARRIER	SEMYA1050-16	Y	1500	0.5	1/2	60	56	93%	120V/60/1	8.4	15	M1.2	5/21/03	1
Sun Valley	BLDG E	FOOD SERVICE	F-17	SPLIT SYSTEM	CARRIER	SEMYA1050-12	Y	1500	0.5	1/3	60	56	93%	120V/60/1	8.4	15	M1.2	5/21/03	1
Sun Valley	BLDG E	FOOTTOP	CU-15	CONDENSING UNIT	CARRIER	3HDOC-018	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/60/3	N/A	N/A		3/21/03	1
Sun Valley	BLDG E	FOOTTOP	CU-16	CONDENSING UNIT	CARRIER	3HDOC-018	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/60/3	N/A	N/A		3/21/03	1
Sun Valley	BLDG C	CLASSROOM	F-1	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	1450	0.5	1/2	100	94	93%	120V/60/1	13.5	15	M1.2	6/27/02	1
Sun Valley	BLDG C	CLASSROOM	F-2	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	1450	0.6	1/2	100	94	93%	120V/60/1	13.5	15	M1.2	6/27/02	1
Sun Valley	BLDG A	MECHANICAL	F-3	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	2000	0.5	3/4	80	74	92%	120V/60/1	17	20	M1.2	6/27/02	1
Sun Valley	BLDG A	ENCLOSURE	F-4	FORCED-AIR FURNACE	CARRIER	NOT USED	Y												1
Sun Valley	BLDG B	CLASSROOM	F-5	FORCED-AIR FURNACE	CARRIER	SEMYA100-15	Y	1500	0.6	1/2	80	74	92%	120V/60/1	13.5	15	M1.2	6/27/02	1
Sun Valley	BLDG B	CLASSROOM	F-6	FORCED-AIR FURNACE	CARRIER	SEMYA100-15	Y	1500	0.6	3/4	100	93	92%	120V/60/1	10.3	20	M1.2	6/27/02	1
Sun Valley	BLDG B	CLASSROOM	F-7	FORCED-AIR FURNACE	CARRIER	SEMYA100-15	Y	1500	0.6	1/2	80	74	92%	120V/60/1	9.5	15	M1.2	6/27/02	1
Sun Valley	BLDG B	CLASSROOM	F-8	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	1500	0.6	1/2	80	74	92%	120V/60/1	9.5	15	M1.2	6/27/02	1
Sun Valley	BLDG B	CLASSROOM	F-9	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	1500	0.6	1/2	80	74	92%	120V/60/1	9.5	15	M1.2	6/27/02	1
Sun Valley	BLDG B	LIBRARY	F-10	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	1500	0.6	1/2	80	74	92%	120V/60/1	9.5	15	M1.2	6/27/02	1
Sun Valley	BLDG B	LAB	F-11	SPLIT SYSTEM	CARRIER	SEMYA030-20	Y	1600	0.6	3/4	80	74	92%	120V/60/1	9.5	15	M1.2	6/27/02	1
Sun Valley	BLDG A	LAB	F-12	FORCED-AIR FURNACE	CARRIER	SEMYA100-16	Y	1450	0.5	1/2	100	94	93%	120V/60/1	9.5	15	M1.2	6/27/02	1
Sun Valley	BLDG A	ENCLOSURE	CU-1	CONDENSING UNIT	CARRIER	3HDOC050	Y	60	N/A	N/A	N/A	N/A	N/A	208V/60/3	NA	32		6/27/02	1
Sun Valley	EVN 1	ELECTRIC HEATER	Q-MARK	CARRIER	CW191204	Y	N/A	N/A	N/A	N/A	N/A	N/A	208V/60/3	NA	44.2		6/27/02	1	
Terra Linda	BLDG P	ROOFTOP	AC-1	AC UNIT	TRANE	Y011834	Y	5400	N/A	N/A	250	N/A	N/A	400V/60/3	NA	NA		1/6/05	1
Terra Linda	BLDG P	ROOFTOP	AC-2	AC UNIT	TRANE	Y011834	Y	5400	N/A	N/A	250	N/A	N/A	400V/60/3	NA	NA		1/6/05	1
Terra Linda	BLDG P	ROOFTOP	AC-3	AC UNIT	TRANE	Y011834	Y	5400	N/A	N/A	250	N/A	N/A	400V/60/3	NA	NA		1/6/05	1
Terra Linda	BLDG P	CONTROL ROOM	AC-P1A	SPLIT SYSTEM	SANYO	K5032	Y	800	N/A	N/A	N/A	N/A	N/A	208V/60/1	NA	NA		1/6/05	1
Terra Linda	BLDG P	CONTROL ROOM	AC-P1B	CONDENSING UNIT	SANYO	C3032	Y	NA	N/A	N/A	N/A	N/A	N/A	208V/60/1	NA	NA		1/6/05	1
Terra Linda	BLDG A	CLASSROOM	F-1	FORCED-AIR FURNACE	CARRIER	SEMYA100-20	Y	1500	0.5	3/4	80	75	93%	120V/60/1	11.1	NA		1/21/05	1
Terra Linda	BLDG A	CLASSROOM	F-2	FORCED-AIR FURNACE	CARRIER	SEMYA100-20	Y	1											

Technical Specifications and SOW Attachment 3

San Rafael High School

FC/HP Summary

[Main Menu](#)[Previous](#)[Floor Plan](#)

Tuesday, 7/22/2003 6:25:34AM

OSA Temp: 60.9 °F

Serving	Zone	Command	Space Temp	Setpoint	SA Temp	Filter/Alarm	Fan	Cg	Htg	Temp Attained
Building G - Studio	F/CU-1	Active	66 °F	66	58 °F		OFF	OFF	OFF	45 69
Building G - Classroom	F/CU-2	Active	68 °F	68	63 °F		ON	OFF	OFF	45 -17
Building G - Computer Lab	F/CU-3	Active	68 °F	67	59 °F		OFF	OFF	OFF	61 103
Building J - Band Room	F-4	Active	69 °F	68	67 °F		ON	N/A	OFF	64 94
Building J - Band Room	F-5	Active	72 °F	68	68 °F		ON	N/A	OFF	68 107
Building J - Band Room Office	F-6	Active	71 °F	68	68 °F		ON	N/A	OFF	68 98
Building J - Band Storage			74 °F							

Page 2 of 2 <<

San Rafael High School

Gym Summary

[Main Menu](#)[Previous](#)[Floor Plan](#)

Tuesday, 7/22/2003 6:23:11 AM

OSA Temp: 61.2 °F

Page 2 of 3 << >>

Setting	Zone	Command	Space Temp	Setpoint	SA Temp	FifteAlarm	Fan	Htg	Temp Attained
----------------	-------------	----------------	-------------------	-----------------	----------------	-------------------	------------	------------	----------------------

Building P - Weight Room	HV-P1	Active	71 °F	68	60 °F		OFF	OFF	70 92
VR	HV-P2	NR	NR °F	NR	NR °F		NR	NR	NR
Building P - East Classroom	HV-P3	Active	70 °F	68	64 °F		OFF	OFF	62 95
Building P - Classroom	HV-P4	Active	72 °F	73	73 °F		ON	ON	75 73
Building P - Girl's Locker Room	HV-P5	Active	69 °F	72	66 °F		OFF	ON	64 66
Building P - Small Gym	HV-P6	Active	65 °F	72	52 °F		OFF	ON	62 52
Building P Team Room	HV-P7	Active	62 °F	67	54 °F		OFF	ON	53 54
Building P - Boy's Locker Room	HV-P8	Active	70 °F	72	61 °F		ON	ON	66 70
Building P - BLR Room Office	HV-P9	Active	71 °F	72	72 °F		OFF	OFF	62 79
Building P - Dance Studio	HV-P10	Active	66 °F	68	66 °F		OFF	ON	60 64
Building P - Big Gym	HV-P11	Active	71 °F	72	68 °F		OFF	OFF	72 74
Building P - Big Gym	HV-P12	Active	70 °F	72	90 °F		ON	ON	64 90
VR	HV-P13	NR	NR °F	NR	NR °F		NR	NR	NR

Setting	Zone	Command	Space Temp	Lockout	SA Temp	Lockout	Fan
Building P - Gym 2	HV-P16	Active	62 °F	120	62 °F		OFF
Building P - Gym 2	HV-P17	Active	0 °F	100	54 °F		OFF

start

Envision for BACtalk -...

Connection Manager

SRCs Device List

6:29 AM



San Rafael High School

Heating Coil Summary

Tuesday, 7/22/2003 6:30:12AM

OSA 60.7 °F

Main Menu
Previous
Floor Plan
<> >>

Serving	Unit	Device ID	Status	Rm Temp.	Space SPT.	Supply Air	Htg
NR	HC-1	2121	NR	NR °F	NR	NR °F	NR %
NR	HC-2	2122	NR	NR °F	NR	NR °F	NR %
NR	HC-3	2123	NR	NR °F	NR	NR °F	NR %
NR	HC-4	2124	NR	NR °F	NR	NR °F	NR %
NR	HC-5	2125	NR	NR °F	NR	NR °F	NR %
NR	HC-6	2126	NR	NR °F	NR	NR °F	NR %
NR	HC-7	2127	NR	NR °F	NR	NR °F	NR %
NR	HC-8	2128	NR	NR °F	NR	NR °F	NR %
NR	HC-9	2129	NR	NR °F	NR	NR °F	NR %
NR	HC-10	2130	NR	NR °F	NR	NR °F	NR %
NR	HC-11	2131	NR	NR °F	NR	NR °F	NR %
NR	HC-12	2132	NR	NR °F	NR	NR °F	NR %
NR	HC-15	2135	NR	NR °F	NR	NR °F	NR %
NR							

HC-14 was Abandoned!

HC-16 was Abandoned!

San Rafael High School


Heating Coil Summary

Tuesday, 7/22/2003 6:30:43AM

OSA 60.7 °F

[Main Menu](#)
[Previous](#)
[Floor Plan](#)
<< >>

	Serving	Unit	Device ID	Status	RM Temp.	Space SPT.	Supply Air	Htg
NR	HC-17	2137	NR	NR °F	NR 	NR °F	NR	%
NR	HC-18	2138	NR	NR °F	NR 	NR °F	NR	%
NR	HC-19	2139	NR	NR °F	NR 	NR °F	NR	%
NR	HC-20	2140	NR	NR °F	NR 	NR °F	NR	%
NR	HC-21	2141	NR	NR °F	NR 	NR °F	NR	%
NR	HC-22	2142	NR	NR °F	NR 	NR °F	NR	%
NR	HC-23	2143	NR	NR °F	NR 	NR °F	NR	%
NR	HC-24	2144	NR	NR °F	NR 	NR °F	NR	%
NR	HC-25	2145	NR	NR °F	NR 	NR °F	NR	%
NR	HC-26	2146	NR	NR °F	NR 	NR °F	NR	%
NR	HC-27	2147	NR	NR °F	NR 	NR °F	NR	%
NR	HC-28	2148	NR	NR °F	NR 	NR °F	NR	%
NR	HC-29	2149	NR	NR °F	NR 	NR °F	NR	%
NR	HC-30	2150	NR	NR °F	NR 	NR °F	NR	%
NR	HC-31	2151	NR	NR °F	NR 	NR °F	NR	%
NR	HC-32	2152	NR	NR °F	NR 	NR °F	NR	%



San Rafael High School

Heating Coil Summary

Tuesday, 7/22/2003 6:31:25AM

OSA 60.7 °F

Main Menu
Previous
Floor Plan

<< | >> | Back | Home | Print | Exit

Serving	Unit	Device ID	Status	Rm Temp.	Space SPT:	Supply Air	Htg	%
NR	HC-33	2153	NR	NR °F	NR []	NR °F	NR	%
Not Assigned								
NR	HC-35	2155	NR	NR °F	NR []	NR °F	NR	%
NR	HC-36	2156	NR	NR °F	NR []	NR °F	NR	%
NR	HC-37	2157	NR	NR °F	NR []	NR °F	NR	%
NR	HC-38	2158	NR	NR °F	NR []	NR °F	NR	%
NR	HC-39	2159	NR	NR °F	NR []	NR °F	NR	%





San Rafael High School

Hot Water System

[Previous](#)
[Main Menu](#)

Tuesday, 7/22/2003 6:26:57 AM	Hot Water System Scheduled ON	Outside Air Lockout	Lag Boiler Delay (Min)	30
DSA 60.9	Hot Water System will enable when scheduled AND Outside air is below lockout temp OR during morning warmup	78	Hot Water Setpoint	170
-Pump Speed				
VFD Manual/Auto				
<input type="checkbox"/> Auto				
VFD Manual Speed Select (%)	100			
Highest Heating Signal (%)	0			
In auto mode, vfd will track highest heating signal!				
Pump Runtime Lead/Lag Setpoint (Hrs)	100			
Lead Pump is:				
Pump 2				
Pump 1 Runtime (Hrs)	89475			
Pump 2 Runtime (Hrs)	89504			
HWP-14	Active			
Pump Delay Off (Sec)	120			





San Rafael High School

Science Summary

[Main Menu](#)
[Previous](#)
[Floor Plan](#)

Wednesday, 7/22/2003 6:28:30AM

OSR Temp: 61.2 °F

Page 1 of 2 << >>

Serving	Zone	Command	Space Temp	Setpoint	SA Temp	Fitter/Adam	Fan	Htg	Temp Attained
NR	HV-F1	NR	NR °F	NR ▲	NR °F	NR	NR	NR	NR
Building F - Classroom SC-105	HV-F2	Active	71 °F	69 ▲	69 °F	OFF	OFF	74	82
Building F - Classroom SC-103	HV-F3	Active	70 °F	67 ▲	61 °F	OFF	OFF	67	77
NR	HV-F4	NR	NR °F	NR ▲	NR °F	NR	NR	NR	NR
NR	HV-F5	NR	NR °F	NR ▲	NR °F	NR	NR	NR	NR
Building F - Classroom SC-102	HV-F6	Active	72 °F	73 ▲	62 °F	OFF	OFF	63	67
NR	HV-F7	NR	NR °F	NR ▲	NR °F	NR	NR	NR	NR
NR	HV-F8	NR	NR °F	NR ▲	NR °F	NR	NR	NR	NR



EF-1 Bathroom Exhaust Fan



CEF-6 Storage Exhaust Fan

Sun Valley Elementary School

Unit Summary - Buildings A,B,C

Tuesday, 7/22/2003 6:45:26AM

OSA 55.3 °F

Serving	Unit	Device ID	Status	Rm Temp.	Space SPT.	Supply Air	Filter/Alarm	Fan Proof	Clg	Htg	Economize
Classroom C9	F-1	1101	Active	67.7 °F	69	62.9 °F		Inactive			0 % 0
Classroom C8	F-2	1102	Active	67.6 °F	68	59.4 °F		Inactive			0 % 0
Classroom C7	F-3	1103	Active	67.0 °F	68	60.2 °F		Inactive			0 % 0
Classroom C6	F-4	1104	Active	67.1 °F	68	60.7 °F		Inactive			0 % 0
Classroom B5	F-5	1105	Active	69.5 °F	69	59.2 °F		Inactive			0 % 0
Kindergarten B1	F-6	1106	Active	68.9 °F	71	57.0 °F		Inactive			0 % 0
Administration - Principal	F-3	1203	Active	71.6 °F	68	60.0 °F		Inactive			0 % 0
Classroom A2	F-7	1207	Active	69.6 °F	68	62.5 °F		Inactive			0 % 0
Classroom A3	F-8	1208	Active	69.5 °F	69	66.5 °F		Inactive			0 % 0
Classroom A4	F-9	1209	Active	68.2 °F	68	63.6 °F		Inactive			0 % 0
Library	F-10	1210	Active	68.6 °F	68	55.3 °F		Inactive			0 % 0
Computer Lab	F-11	1211	Active	70.9 °F	72	56.1 °F		Inactive			0 % 0
Resources	F-12	1212	Active	69.3 °F	65	55.1 °F		Inactive			0 % 0

Main Menu

Previous

Floor Plan

>>



Sun Valley Elementary School

Unit Summary - Building D

[Main Menu](#)[Previous](#)[Floor Plan](#)

Tuesday, 7/22/2003 6:46:11AM

OSA 55.4 °F

Serving	Unit	Device ID	Status	Rm Temp.	Space SPT.	Supply Air Filter/Alarm/Fan Proof	Ctg	Htg	Attains
Classroom 10	HP-1	1301	Active	69.2 °F	70	79.3 °F		Active	Inactive
Classroom 11	HP-2	1302	Active	68.9 °F	68	70.0 °F		Inactive	Inactive
Classroom 12	HP-3	1303	Active	67.6 °F	68	69.6 °F		Inactive	Inactive
Classroom 13	HP-4	1304	Active	68.2 °F	68	70.6 °F		Inactive	Inactive
Classroom 14	HP-5	1305	Active	67.5 °F	68	68.4 °F		Inactive	Inactive
Classroom 15	HP-6	1306	Active	67.9 °F	68	68.3 °F		Inactive	Inactive
Classroom 16	HP-7	1307	Active	67.6 °F	68	63.0 °F		Inactive	Inactive
Classroom 17	HP-8	1308	Active	70.6 °F	71	70.1 °F		Inactive	Inactive
Classroom 18	HP-9	1309	Active	68.0 °F	69	64.8 °F		Inactive	Inactive
Classroom 19	HP-10	1310	Active	69.6 °F	70	66.7 °F		Inactive	Inactive
Classroom 20	HP-11	1311	Active	68.9 °F	69	65.9 °F		Inactive	Inactive
Classroom 21	HP-12	1312	Active	68.3 °F	68	67.0 °F		Inactive	Inactive
Classroom 22	HP-13	1313	Active	68.9 °F	69	73.5 °F		Inactive	Inactive



Terra Linda High School

Building M Second Floor Summary

Tuesday, 7/22/2003 5:55:57 AM

OSA Temp: 71.5 °F

[Main Menu](#)
[Previous](#)
[Floor Plan](#)

Page 2 of 2 <<

	Setting	Zone	Command	Space Temp	Setpoint	SA Temp	Fan	Htg	Cfg	Temp Attained
Terra Linda Classroom 401	F-2-1	Active	72 °F	70	69 °F		OFF	OFF	84	108
VR	F-2-2	NR	NR °F	NR	NR °F		NR	NR	NR	NR
Terra Linda Classroom 405	F-2-3	Active	71 °F	70	72 °F		OFF	OFF	53	87
Terra Linda Classroom 407	F-2-4	Active	72 °F	70	70 °F		OFF	OFF	61	111
Terra Linda Classroom 409	F-2-5	Active	72 °F	70	69 °F		OFF	OFF	52	108
Terra Linda Classroom 411	F-2-6	Active	72 °F	70	69 °F		OFF	OFF	57	104
Terra Linda Classroom 402	F-2-7	Active	72 °F	70	71 °F		ON	OFF	51	110
Terra Linda Classroom 404	F-2-8	Active	72 °F	70	69 °F		OFF	OFF	52	110
Terra Linda Classroom 406	F-2-9	Active	73 °F	70	72 °F		OFF	OFF	55	110
Terra Linda Classroom 408	F-2-10	Active	71 °F	73	70 °F		OFF	OFF	49	115
Terra Linda Classroom 410	F-2-11	Active	71 °F	70	69 °F		OFF	OFF	58	103
Terra Linda Classroom 412	F-2-12	Active	73 °F	70	72 °F		OFF	OFF	47	61
Terra Linda Classroom 54	F-3-1	Active	73 °F	69	73 °F		OFF	OFF	51	97
Terra Linda Classroom 52	F-3-2	Active	72 °F	70	72 °F		OFF	OFF	54	101
Terra Linda Classroom 50	F-3-3	Active	72 °F	69	70 °F		OFF	OFF	81	103

Bahia Vista Elementary School

Building B Furnace Summary

OSA Temp: 0.0 °F

Setting	Properties	Zone	Command	Space Temp	Sepoint	SA Temp	Fan	Filt	Econ.	Htg	Temp Affirmed
Classroom 1B18		F-1A	Auto	71.0	72.0 ↘	70.0 °F	OFF	●	OFF	OFF	77 112
Classroom 1B19		F-2A	Auto	70.5	60.0 ↗	69.9 °F	OFF	●	OFF	OFF	78 118
Classroom 1B20		F-3A	Auto	70.5	61.0 ↗	71.2 °F	OFF	●	OFF	OFF	79 118
Classroom 1B21		F-4A	Auto	68.5	68.0 ↗	67.0 °F	OFF	●	OFF	OFF	77 125
Classroom 1B22		F-5A	Auto	68.5	60.0 ↗	67.0 °F	OFF	●	OFF	OFF	80 121
Classroom 1B23		F-6A	Auto	68.0	60.0 ↗	67.1 °F	OFF	●	OFF	OFF	78 129
Classroom 2B14		F-7A	Auto	67.0	70.0 ↘	68.2 °F	OFF	●	OFF	OFF	78 118
Classroom 2B13		F-8A	Auto	69.5	60.0 ↗	68.5 °F	OFF	●	OFF	OFF	78 121
Classroom 2B12		F-9A	Auto	71.5	71.0 ↘	69.4 °F	OFF	●	OFF	OFF	79 120
Classroom 2B11		F-10A	Auto	69.5	68.0 ↗	70.0 °F	OFF	●	OFF	OFF	81 114
Classroom 2B15		F-11A	Auto	72.5	67.0 ↗	67.6 °F	OFF	●	OFF	OFF	80 124
Classroom 2B16		F-12A	Auto	69.5	70.0 ↘	65.9 °F	OFF	●	OFF	OFF	80 121
Classroom 2B17		F-13A	Auto	67.5	72.0 ↘	64.9 °F	OFF	●	OFF	OFF	81 118

Bahia Vista Elementary School

Building C Furnace Summary

[Main Menu](#)
[Previous](#)
[Floor Plan](#)

Today, 7/22/2003 6:50:04AM

OSA Temp: 0.0 °F

	Sensor	Properties	Zone	Command	Space Temp	Sefpoint	SA Temp	Ffilter	Fan	Econ.	Htg	Temp Attained
Kindergarten 1C01	F-1C	<input type="checkbox"/> Auto		69.0	60.0	68.0 °F		<input checked="" type="checkbox"/>	ON	OFF	OFF	82 60
Kindergarten 1C14	F-2C	<input type="checkbox"/> Auto		69.5	70.0	68.1 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	80 119
Kindergarten 1C07	F-3C	<input type="checkbox"/> Auto		69.0	75.0	67.6 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	78 121
NR	F-4C	<input type="checkbox"/> NR		NR	NR	NR °F		<input checked="" type="checkbox"/>	NR	NR	NR	NR
Head Start 1C08	F-5C	<input type="checkbox"/> Auto		67.5	64.0	68.3 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	77 119
Even Start 1C21	F-6C	<input type="checkbox"/> Auto		69.5	60.0	68.1 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	80 124
Head Start 1C12	F-7C	<input type="checkbox"/> Auto		63.5	74.0	61.8 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	78 126
Classroom 2C01	F-8C	<input type="checkbox"/> Auto		70.5	72.0	68.4 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	63 107
Classroom 2C04	F-9C	<input type="checkbox"/> Auto		69.0	60.0	67.0 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	81 106
Classroom 2C02	F-10C	<input type="checkbox"/> Auto		67.5	60.0	66.2 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	78 119
Classroom 2C05	F-11C	<input type="checkbox"/> Auto		71.0	65.0	67.6 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	82 117
Classroom 2C03	F-12C	<input type="checkbox"/> Auto		69.5	71.0	68.0 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	78 114
Classroom 2C06	F-13C	<input type="checkbox"/> Auto		69.5	71.0	67.7 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	75 109
RSP 2C07	F-14C	<input type="checkbox"/> Auto		71.0	60.0	68.7 °F		<input checked="" type="checkbox"/>	OFF	OFF	OFF	82 122

Bahia Vista - Device 6135 (Hot Water System)

Actalk Edit View Tools Help

Previous

Schedule Active

Auto

OSA Lockout SP

OSA Temp


OSA Enabled Yes

Boiler Enable On

boiler ready to run On

HWRI temp
130.7

131.5
Lwg Boiler temp



Boiler Firing Mode On

Lead Pump Pump-1

HPA1 Enable On

HPA1 proof On 50.9 gpm

HPA2 Enable Off

HPA2 proof Off 1.1 gpm

Low OSA sp
High OSA sp
max HW temp
min HW temp

HWIS temp SP
180.0 °F
3-way valve
84.3 %

start

Connection Man...

Bahia Vista - Dev...

EVES Device list...

SCS Device list

6:51 AM

Bahia Vista Elementary School

VAV Summary 1st floor

[Main Menu](#) | [More >>](#)
[Previous](#) | [Floor Plan](#)

		OSA Temp: 0.0 °F		Space Temp.		Current CFM		Desired CFM		SAT Temp.		HWY %	
	Location	Unit	Status	Setpoint	Space Temp.								
	Office 1B12	DI # 6119	VAV 1-1	Auto	72	68	*F	142	600	73	*F	100	%
	Office 1B14	DI # 6120	VAV 1-2	Auto	74	71	*F	282	430	74	*F	100	%
	Admin 1B01	DI # 6121	VAV 1-3	Auto	74	71	*F	465	1600	77	*F	100	%
	Office 1B05	DI # 6122	VAV 1-4	Auto	75	72	*F	398	720	75	*F	100	%
	Library 1B16	DI # 6123	VAV 1-5	Auto	73	69	*F	308	800	74	*F	100	%
	Women's RR 1B24	DI # 6124	VAV 1-6	Auto	70	68	*F	376	500	71	*F	0	%
	Nursing Station 1B09	DI # 6125	VAV 1-7	Auto	73	72	*F	114	220	73	*F	0	%
	Principal's Office 1B03	DI # 6126	VAV 1-8	Auto	74	69	*F	196	300	79	*F	100	%
	Conf. Room 1B02	DI # 6127	VAV 1-9	Auto	70	70	*F	89	500	71	*F	0	%

Bahia Vista Elementary School

VAV Summary 2nd floor

[Main Menu](#)
[Previous](#)
[Floor Plan](#)

					OSA Temp: 0.0 °F						
	Location	Unit	Status	Setpoint	Space Temp.	Current CFM	Desired CFM	SA Temp.	H/W %		
	Computer Room 2B08	DI # 6128	VAV 2-1	Auto	73	71 °F	235	783	69 °F	67	%
Lounge 2B05	DI # 6129	VAV 2-2	Auto	72	72 °F	283	600	73 °F	0	0	%
Workroom 2B04	DI # 6130	VAV 2-3	Auto	74	73 °F	310	750	76 °F	0	0	%
Conference 2B01	DI # 6131	VAV 2-4	Auto	66	68 °F	308	750	77 °F	0	0	%
Office 2B02	DI # 6132	VAV 2-5	Auto	72	73 °F	125	750	73 °F	0	0	%
Office 2B03	DI # 6133	VAV 2-6	Auto	72	73 °F	248	750	73 °F	0	0	%
Women's RR 2B20	DI # 6134	VAV 2-7	Auto	70	69 °F	556	750	72 °F	0	0	%

Davidson MS - Envision for BACtalk - SYSERCO/SR_DAVMS

BACtalk Edit View Tools Help



Davidson Middle School Air Handler Summary

Main Menu
Previous

uesday, 7/22/2003 6:40:10AM

OSA Temp: 56.7 °F

Serving	Device ID	Zone	Command	SA Temp	Filtter/Alarm	Fan	Econ
AHU-1	5109	AH-1	Active	71.8 °F	■	ON	0 6 Op



Davidson Middle School

Furnace Summary

Wednesday, 7/22/2003 6:42:58AM

OSA Temp: 57.3 °F

Serving	Zone	Command	Space Temp	Setpoint	SA Temp	Fitter/Alarm	Fan	Htg	Temp Attained
* no entry *	F-7	* no entry *	* no °F	* no °F	* no °F	*	*	* no	* no * no * no
Room 30	F-1	Active	70 °F	68 °F	69 °F	OFF	OFF	67	116
Room 31	F-2	Active	73 °F	73 °F	76 °F	OFF	OFF	62	117
Room 32	F-3	Active	70 °F	68 °F	68 °F	OFF	OFF	66	126
* no entry *	F-4	* no entry *	* no °F	* no °F	* no °F	*	* no	* no * no	* no
Room 34	F-5	Inactive	69 °F	68 °F	66 °F	OFF	OFF	77	116
* no entry *	F-6	* no entry *	* no °F	* no °F	* no °F	*	* no	* no * no	* no

[Main Menu](#)
[Previous](#)



Davidson Middle School

Heating Hot Water System

[Main Menu](#)
[Previous](#)

Wednesday, 7/22/2003 6:43:46AM

[Properties](#) [Schedule](#)5110 | [ON](#)

Auto

Serving	Device ID	Boiler	Status HwP	Cmd	C SW	Spf Auto	Spf Manual	Spf Current	HWS Temp	HWR Temp	Mixer Valve
Hot Water System	5110	<input checked="" type="radio"/>	<input type="radio"/>	On	<input type="radio"/>	170.0 °F	<input checked="" type="radio"/>	170.0 °F	142.1 °F	141.3 °F	100.0 %

Boiler Control

 Force Hot Water System On On
 Valve Signal Reverse Hot Water Valve Action DSA Lockout Man Loop %
100.0 Curr Loop % HwP1
 HwP2 Current Lead HwP Manual Lead HwP Auto Lead HwP Pump Xover Hs Pump Shutdown Delay (min) Pump Alarm 1 Pump Alarm 2 Reset Alarms start Envision for BAC... Connection Man... BACTalk MS - E... SR 6:43 AM
OSA Temp: 57.4 °F
Sysco PH_091...
SRS Device list
DMS Device list

Davidson Middle School

Reheat Coil Summary

Tuesday, 7/22/2003 6:41:37AM

OSA 57.2 °F

[Main Menu](#)
[Previous](#)

Serving	Unit	Device ID	Status	Rm Temp.	Space SPT.	Supply Air	Htg	Rev Action
Reception A-01	RHC-1	5101	Active	70.2 °F	68	71.9 °F	0	%
Principal A-08	RHC-2	5102	Active	70.2 °F	70	71.9 °F	0	%
Teachers Lounge A-25	RHC-3	5103	Active	72.7 °F	70	72.7 °F	0	%
Conference Room A-10	RHC-4	5104	Active	73.0 °F	67	86.7 °F	0	%
Attendance A-02	RHC-5	5105	Active	70.8 °F	68	71.7 °F	0	%
Counseling A-19	RHC-6	5106	Active	69.0 °F	65	71.9 °F	0	%
Suspension A-22	RHC-7	5107	Active	69.9 °F	69	71.7 °F	0	%
Classroom A-24	RHC-8	5108	Inactive	72.1 °F	67	80.5 °F	0	%



x Help, click Help Topics on the Help Menu.

 StartEnvision for BAC...  Connection Man...

859,565

 DMS Device list ...

859,565

 SRCS Device list ...

6:41 AM

Glenwood Elementary School

Building G Summary

[Main Menu](#)[Previous](#)[Floor Plan](#)

Tuesday, 7/22/2003 6:38:04AM

OSA Temp: 62.7 °F

Page 1 of 1 <<


Serving	Zone	Command	Space Temp	Setpoint	SA Temp	Fitter/Dam	Fan	Htg	Econ.	Temp Attain
---------	------	---------	------------	----------	---------	------------	-----	-----	-------	-------------

JR	F-1	NR	NR °F	NR °F	NR °F	NR °F	NR	NR	NR	NR
Glenwood Classroom 18	F-2	Active	70 °F	72 °F	69 °F	69 °F	ON	OFF	20 %	71 108
Glenwood Classroom 17	F-3	Active	69 °F	66 °F	66 °F	68 °F	OFF	OFF	0 %	69 140
Glenwood Classroom 16	F-4	Active	71 °F	72 °F	72 °F	88 °F	OFF	OFF	0 %	65 125
Glenwood Classroom 15	F-5	Active	71 °F	66 °F	66 °F	68 °F	OFF	OFF	0 %	68 123
Glenwood Classroom 14	F-6	Active	69 °F	67 °F	67 °F	67 °F	OFF	OFF	0 %	64 108
Glenwood SciArt 20	F-8	Active	69 °F	70 °F	70 °F	83 °F	OFF	OFF	0 %	0 126
Glenwood Classroom HO3	F-9	Active	69 °F	73 °F	73 °F	66 °F	OFF	OFF	0 %	60 104



Exit Help

Print View Tools Edit



San Rafael High School Air Handler Summary

Main Menu

Previous

Floor Plan

July 7/22/2003 6:01:58AM

OSA Temp: 56.3 °F

Page 1 of 1

Serving	Device ID	Zone	Command	SA Temp	Filter/Alarm	Fan	Htg	Econ
Air Handler 1	2120	AC-1A	Active	52.5 °F	<input checked="" type="checkbox"/>	ON	100 %	25 % Op



San Rafael High School

FC/HP Summary

[Main Menu](#)[Previous](#)[Floor Plan](#)

Tuesday, 7/22/2003 6:26:22AM



OSA Temp: 60.9 °F

Page 1 of 2 << >>

Serving	Zone	Command	Space Temp	Setpoint	SA Temp	Ffilter/Alarm	Fan	Comp	RV Mode	Temp Attained
Library	FC/HP-1	Active	71 °F	70	73 °F		ON	OFF		48 78
Library	FC/HP-2	Active	71 °F	70	72 °F		OFF	OFF		74 72
Library	FC/HP-3	Active	71 °F	70	73 °F		OFF	OFF		54 85
Library	FC/HP-4	Active	71 °F	70	71 °F		OFF	OFF		52 95
Library Workroom	FC/HP-5	Active	72 °F	68	58 °F		ON	ON		58 77
Building LA-213	FC/HP-7	Active	67 °F	70	68 °F		N/A	OFF		74 66
VR	FC/HP-8	NR	NR °F	NR	NR °F		NR	NR		NR NR
Building G - Office	FC/HP-9	Active	69 °F	67	70 °F		OFF	OFF		48 93
Building G - Office			NR °F							

San Rafael High School Building G


ay. 7/21/2003 7:41:24AM OSA 63.6 °F



San Rafael High School

Building J - Band Room

Main Me
Previous







talk Edit View Tools Help


San Rafael High School Campus Map

Monday, 7/21/2003 7:42:12AM

OSA 63.6 °F



Main Me
Previous




San Rafael High School
Building LA - Main Level

Main Me

Previous

ay, 7/21/2003 7:41:06AM OSA 63.6 °F

<< :>>



start

Envision for ... Connection ...

San Rafael H... SRHS LA Bid ...


My Computer

Control Panel

7/41

San Rafael High School Building LA - Upper Level

ay, 7/21/2003 7:40:43AM OSA 63.6 °F




Sun Valley Elementary School

Building A Floor Plan


Top Dis
<< >>

OSA 65.9 °F
lay. 7/21/2003 10:46:34AM



Sun Valley Elementary School Building B Floor Plan

Top Dis
<< >>




Top Dis
<< >>

Sun Valley Elementary School

Building C Floor Plan

Apr. 7/21/2003 10:47:27AM OSA 65.9 °F



Sun Valley Elementary School Building D Floor Plan

[Top](#) [Dis](#)
[Previo](#)


May 7/21/2003 10:47:42AM OSA 65.9 °F

Second Floor

Classroom 16	Classroom 17	Classroom 18	Classroom 19	Classroom 20	Classroom 21	Classroom 22
HP-7	HP-8	HP-9	HP-10	HP-11	HP-12	HP-13
70.1	70.9	70.8	71.5	70.8	70.9	70.9

First Floor

Classroom 15	Classroom 14	Classroom 13	Classroom 12	Classroom 11	Classroom 10
HP-6	HP-5	HP-4	HP-3	HP-2	HP-1
70.2	69.5	70.1	70.2	69.5	71.5




Main Me
Previous

Glenwood Elementary School Building G Floor Plan

Monday, 7/21/2003 12:47:03PM

OSA Temp: 67.9 °F






File Edit View Tools Help

Main Me
Previous

Glenwood Elementary School Building H Floor Plan

Monday, 7/21/2003 12:45:49PM

OSA Temp: 67.8 °F



start

Envision for BACtalk - ...

Glenwood Elem. - En... Connection Manager

Sysco/SR_Glenwood_09182018

12:45